



**WORK SCOPE**

- (A) CLEANLY CUT EXISTING LATERAL ON ROAD SIDE OF EXISTING CLEANOUT AND AT NEW TIE-IN LOCATION.
- (B) REMOVE VERTICAL CLEANOUT APPURTENANCES AND SECTION OF EXISTING SEWER LATERAL UP TO NEW TIE-IN LOCATION.
- (C) INSTALL NEW SECTION OF SEWER LATERAL INCLUDING NEW CLEANOUT, WYE, BEND AND RELATED APPURTENANCES. (SEE GENERAL NOTE 2)
- (D) TIE-IN TO EXISTING HOUSE SIDE SEWER LATERAL USING AN APPROPRIATE COUPLING CONNECTION OR REPAIR SLEEVE AS NEEDED.

**NOTES:**

1. LOCATION OF NEW CLEANOUT SHALL BE AS NOTED ON THE PLANS OR IN THE UTILITY STATEMENT, OR AS DIRECTED BY THE SUSSEX COUNTY INSPECTOR.
2. SLOPE OF NEW SECTION OF SEWER LATERAL SHALL MATCH EXISTING UNLESS DIRECTED OTHERWISE BY THE SUSSEX COUNTY INSPECTOR.
3. REMOVAL AND/OR TIE-IN LOCATIONS SHALL BE A MINIMUM OF 2 FEET FROM EXISTING PIPE JOINTS.
4. WORK SHALL BE SCHEDULED AND PERFORMED IN A MANNER TO MINIMIZE SEWER SERVICE DISRUPTION.
5. REFER TO SUSSEX COUNTY DETAIL S-2.01 FOR NEW SEWER LATERAL CLEANOUT.

**GENERAL NOTES:**

1. THIS DETAIL APPLIES TO REQUIRED HORIZONTAL RELOCATION OF A SEWER CLEANOUT DUE TO CONFLICT WITH ROADWAY OR OTHER SITE CONSTRUCTION ACTIVITIES.
2. NEW MATERIALS PROPOSED TO BE USED FOR LATERAL EXTENSION SHALL BE SUBJECT TO COUNTY REVIEW AND APPROVAL. "FERNCO" TYPE ADAPTORS AND COUPLINGS ARE NOT PERMITTED.



SUSSEX COUNTY  
ENGINEERING DEPARTMENT

APPROVED: *[Signature]*  
SUSSEX COUNTY ENGINEER

**SEWER LATERAL  
CLEANOUT RELOCATION**

DETAIL  
S-2.11

LAST REVISED:  
10/11/2023