



NOTE: FOR APPLICATIONS WHERE A GRINDER PUMP STATION IS NOT INSTALLED AS PART OF THE WORK, CONTRACTOR SHALL FURNISH AND INSTALL A SCHEDULE 80 PVC MALE THREADED PLUG INTO THE END OF VALVE ASSEMBLY FOR FUTURE CONNECTION.



SUSSEX COUNTY
ENGINEERING DEPARTMENT

APPROVED: *James Chedoke*
SUSSEX COUNTY ENGINEER

LATERAL ISOLATION
VALVE

DETAIL
S-5.03

DATE ISSUED:
1/18/2023